Bruhath Bangalore Mahanagara Palike

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Detailed Estimate for Providing SV Street light fittings/Timer Controler Switches/ACSR Controle Wire and Street lighting accessories in Ward No-01

Sl No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In Words
		KPWD (Ele) S.R.2014-15			
1	125	Supplying High pressure sodium vapour street light luminaire suitable for use with high pressure sodium vapour lamp with integrated control gear and grey colr powder coated. The fitting shall be non corrosive pressure die cast aluminium housing with high purity anodized aluminium housing with EPDM Gaskets suitable for Outer Dia of pole 40 mm -60 mm. Cable entry through a cable gland with toggle clips. IP65 protection for both optical & electrical compartment. Bottom cover may be with poly carbonate/tempered/ toughened glass.Luminaire efficiency should be > 60 % and ambient temperature >35 deg C. High Intensity Discharge electro magnetic ballast with copper winding of Orthocyclic winding coil. Class H insulated dual coated copper wire. Complaince to IEC 61347-2-9 Safety & IEC 60923-Performance. Winding Temperature rise " T=70 deg C. Luminaire shall be suitable to operate on 230/250 V 50 Hz AC supply finish including wiring , Ignitor, condenser, SS Toggles for opening front hingeable glass 250 Wattsa) Group 'A'	Each	5450.00	Rupees Five Thousand Four Hundred and Fifty only
2	125	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. 17.1.2)Using 32mm dia G.I.pipe	Each	280.00	Rupees Two Hundred and Eighty only
3	1250	Supplying of 1.1 KV grade Aerial Bunched Cable Stranded and Compacted Aluminium Phase Conductor and Stranded Messenger Conductor with all aluminium Alloy, Phase Conductor is insulated with XLPE Compound, Insulated Messanger with SpecifiedIS-14255:1995 & confirming to GTP of Group A 2X16+1X25Sqmm	mtr	68.50	Rupees Sixty Eight and Fifty Paise only
4	1250	Striniging of 1.1 KV grade aerial bunched 3 core cable of XLPE insulation standard aluminium conductor standard around a weather resistant black XLPE insulated AAA messanger wire (3X 25 Sq mm + 1X 16 sqmm + 1X 25Sqmm + 1X 35 sqmm)	P/Mtr	8.00	Rupees Eight only
5	5	Dead End Clamp/ Anchor clamps assembly 25 to 95 sqmm bear messanger (Standard Stock materials 2010-11)	Nos	130.00	Rupees One Hundred and Thirty only
6	50	suspension clamp assemblly 25 to 95 sqmm bear messanger (Standard Stock materials 2010-11)	Nos	210.00	Rupees Two Hundred and Ten only
7	50	Errection of suspension clamp 25 to 95 sqmm bear messanger (Labour charges 2010-11)	Nos	80.00	Rupees Eighty Five only
8	5	Errection of Anchor clamp 25 to 95 sqmm bear messanger (Labour charges 2010-11)	Nos	80.00	Rupees Eighty Five only
9	150	Supplying and fixing ..... including all Hardwares etc complete as per the standard technical specification e) RCC Clamp	Each	70.00	Rupees Seventy only

10	2250	Supplying and stringing of ACSR Conductor (6/2.59mm Al+1/2.59mm steel)	Mtr	20.00	Rupees Twenty only
11	130	Supplying and Fixing….. including all Hardwares etc complete as per the Standard technical Specification. 5.9.1) 1.1 KV Pin insulator	Each	40.00	Rupees Forty only
	20	5.9.5 No. 8 Strain Insulator	Each	13.00	Rupees Thirteen only
12	150	Supply and fixing of …… cross arm including all Hardwares compete as per the standard technical specification.b) 2 Pin 45x45x5mm-510mm	Each	200.00	Rupees Two Hundred only
13	10	Supplying and fixing of Solar Lux level Street light control switch three phase including suitable capacity contactor 12 KW **Specification of Timer:**The ON & OFF timing is based on astronomical twilight data so it helps in the precise switching ON & OFF of the lighting load.The ON & OFF pre-programmed time intervals can be modified by the user. Micro processor based electronic timer consisting of LCD, builtin Real Time Clock and keypad with options to operate Electronic contactor in programmable mode or astronomical mode or depending on light intensity(lux level using IR sensor) **Specification of Electronic Contactor: 125Amps Electronic contactor with suitable heat sink to withstand load** The Electronic Contactor unit is controlled by the MCU and the same is mounted on an aluminium heat sink to dissipate the heat and thereby keep the junction temperature under the safe operating limit. The Electronic Contactor is connected to the lighting load and will provide better switching reliability and trouble free operation with longer life since there is no moving parts. The Electronic Contactor's are resistant to vibration, shock and humidity. It will not generate RFI,EMI and there is no arcing of contacts. Features:Reliable and Safe Switching. Input :170V – 280V AC Displays ON & OFF timing. Frequency : 50Hz ± 5% EC Turn On Time : 40 msec EC Turn OFF Time : 80 msec EC Input Resistance : 20K Ohm Programmable ON & OFF timing.	mtr	10000.00	Rupees Ten Thousand only
14	10	Supply and Installation/Fixing/ Provision of Outdoor type Thermoplastic modular panel enclosure with transparent polycarbonate lid, shock proof, IP 65 (Weather Proof) rust proof, water proof, corrosion proof having internally embedded gasket on both lid and flap suitable to fix. Single phase/three phase energy meter in suitable base plate and having a provision for Fuse/MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility. 300x300x214mm	each	3800.00	Rupees Three Thousand and Eight Hundred only
15	10	Supplying and fixing angle iron frame work fabricated out of M.S angle iron… and M.S. flat… with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.	mtr	200.00	Rupees Two Hundred only
16	20	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. 5-32 Amps SP	each	200.00	Rupees Two Hundred only
17	10	Supply and Installation/Fixing/Provision for mounting of HRC Fuse /MCB with suitable connector/teminal for 3 Ph/1 Ph connections with Loop-in & Loop-Out terminals for 10 Sqmm/25 sqmm 3.5 C Al/AR/Cu/AR Cable and branchout 2.5 Sqmm 2 Core Al/Cu PVC insulated cable, enclosure, which should be shock proof, safe IP 65 (Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP 65 Thermoplastic, Polyamide glands and /or grommets.	Each	1900.00	Rupees One Thousand and Hundred Nine only

	4000	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc., and fixing on existing wood or metal box using N.F.screws.	SqCm	0.22	Rupees Zero and Twenty Two Paise only
19	60	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes 25 sqmm long barrel	Each	18.00	Rupees Eighteen only
20	65	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanized, steel strip confirming to IS-3975:1990 (No of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1998 & confirming GTP of GROUP-A. 3.5 core 25 sqmm	mtr	140.00	Rupees One Hundred Forty only
21	65	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required.II. On wall /Structure 25 sqmm to 75 sqmm	mtr	30.00	Rupees Thirty only

I am prepared to take up the above work at the Rates Quoted by me in Schedule-B

CONTRACTOR

EXECUTIVE ENGINEER (ELE)
Yelahanaka Zone, BBMP